

Schedule of work.

Name of work : Telephone cable laying in the TRC Building of IACS.

Sl. No.	Description.	Quantity	Unit	Rate(Rs.)	Amount(Rs.)
1	Supplying and laying of 0.5 mm dia, 10 pair, annealed copper conductor,FR-PVC insulated armoured telephone cable.	60	Meter		
	Make : Finolex/Netco/Nicco/Delton				
2	Supplying of laying 0.5 mm dia, 5 pair, annealed copper conductor,FR-PVC insulated armoured telephone cable.	360	Meter		
	Make : Finolex/Netco/Nicco/Delton.				
3	Supplying and laying of 0.5 mm dia, 2 pair, annealed copper conductor,FR-PVC insulated un-armoured telephone cable.	270	Meter		
	Make : Finolex/Netco/Nicco/Delton.				
4	Supplying and laying of following size medium class PVC conduit along with all accessories like socket,bend, couplers etc. in surface/recess including cutting the wall and making good the same, complete as required				
a)	20 mm dia.	250	Meter		

Sl. No.	Description.	Quantity	Unit	Rate(Rs.)	Amount(Rs.)
5	Supplying and fixing of 50 pair, 2 mm thick, CRCA sheet steel telephone junction box,duly power coated painted, dust protected along with 1 X 50 pair base and krone modules fitted inside, including connection, testing & commissioning etc. as required.	1	Nos.		
	Make : Krone.				
6	Supplying and fixing of 20 pair, 2 mm thick, CRCA sheet steel telephone junction box,duly power coated painted, dust protected along with 1 X 20 pair base and krone modules fitted inside, including connection, testing & commissioning etc. as required.	3	Nos.		
	Make : Krone.				
7	Supplying and fixing of single pair rozette box.	100	Nos.		
8	Supplying and fixing of RJ-11 socket	200	Nos.		
9	Supplying and fixing telephone handset with all accessories	30	nos.		
	Make: Panasonic-KXTS-400SXB / BPL-6390				
10	Krone make telephone module (White colour)	100	nos.		
				Total :	
Rupees.....Only					
NOTE:The quoted rate shall be inclusive of all taxes & duties, levies, cess etc i/c GST also. Nothing extra will be paid to the Contractor except the accepted rate.					
	GST No:				
	SAC code:				
	CGST@....6.....% considered in the above BOQ				
	SGST@.....6.....%Considered in the above BOQ				