

Estimate cum schedule of work					
Name of Work: Supply, installation, testing and commissioning of UPS and Servo controlled voltage stabilizer along with its accessories for installation of EPR instrument.					
Sl.No.	Item description.	Quantity	Unit	Rate (Rs.)	Amount (Rs.)
1	Supply, installation, testing and commissioning of 6KVA, single phase, double conversion online UPS, as per IEC 62040-3, according to the technical data sheet attached with the NIT, with one year warranty obligation.	1	No.		
	Make: Vertiv-liebert /Emerson /Schneider-APC/Legrand-Numeric				
2	SITC of 20 KVA, 3 Phase Servo controlled volatge stabilizer, as per IS 9815 : 1994, according to the technical specification attached with the NIT, with 1-year warranty obligation.	1	No.		
	Make: Vertiv-liebert /Emerson /Schneider-APC/Legrand-Numeric				
3	Wiring for circuit/submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor,single core cable in surface/ recessed medium class PVC conduit as required.				
a)	4 X 10 sq.mm + 2 X 6 sq.mm earth wire.	8	Metre		
b)	2 X 10 sq.mm. + 1 X 6 sq mm earth wire.	8	Metre		
	Make: Finolex/KEI/Glosted/Havells				
4	Supply, Installation,Testing & Commissioning of 26Ah each, 12V SMF,VRLA battery along with supplying of 10 Sq.mm PVC insulated flexible copper wire for interconnection , jumper arrangement and termination, as required. (with 3-years warranty obligation)	20	Nos.		
	Make: Exide /Quanta				
5	Supplying of MS angle iron battery rack with suitable dimention for mounting 20 nos. 26AH batteries.	1	No.		
			Total :		
Rupees.....Only					
NOTE:The quoted rate shall be inclusive of all taxes & duties, levies, cess etc i/c GST also. Nothing extra will be paid to the Contractor except the accepted rate.					
GST No:					
HSN/SAC code:					
	CGST@ 14% for batteries and 9% for Rack and other electrical items are considered in the above BOQ				
	SGST@ 14% for batteries and 9% for Rack and other electrical items are considered in the above BOQ				