

PRICE BID & SCHEDULE OF WORK					
NIT No.- IACS/WS/SB/2016-17/94, Dated 21-02-2017					
Name of Work: Electrical Work for Room no 19B of IACS, Jadavpur.					
Item No.	Description of Works	Qty.	Unit	Rate (Rs.)	Amt. (Rs.)
1	Wiring for circuit/submain/power plug wiring along with earth wire with the following sizes of FRLS PVC insulated copper conductor single core cable in surface/recessed medium class PVC conduit as required.				
(a)	2x1.5 sq.mm. + 1x1.5 sq.mm. earth wire	10	Mtrs.		
(b)	2x4 sq.mm. + 1x4 sq.mm. earth wire	35	Mtrs.		
2	Supplying and fixing of following size/modules GI box along with modular base & cover plate for modular switches in recess etc. as required.				
(a)	2 Module	1	No.		
(b)	8 Module	4	Nos.		
(c)	3 Module	4	Nos.		
3	Supplying & Fixing of following modular switch/socket on the existing modular plate and switch box including connections but excluding plate etc. as required.				
(a)	5 pin 6A socket outlet	4	Nos.		
(b)	5 amp switch	4	Nos.		
(c)	6 pin 15/16A socket outlet	8	Nos.		
(d)	15/16 amp switch	8	Nos.		
(e)	3 pin 16A Plug Top	1	Nos.		
4	Supplying & Fixing of modular type 20 Amp A.C. starter switch on existing GI box complete recessed in wall.	1	No.		
			Total (Rs.)		