

Price Bid & Schedule of Works						
Name of Work: Renovation of Internal Electrification Work for Room no -159B of IACS.						
Item No.	Description	Qty	Unit	Rate (Rs.)	Amount (Rs)	Remarks
1	Wiring for light point / fan point / exhaust fan point / call bell point with 1.5sq.mm FRLS PVC insulated copper conductor single core cable in surface / recessed medium class PVC conduit, with modular switch, modular plate , suitable GI box and earthing the point with 1.5 sq.mm. FRLS PVC insulated copper conductor single core cable etc. as required.					
	Group C (as per CPWD Categorisation)					
a)	Light point	10	Point			
b)	Fan point	4	Point			
2	Wiring for circuit/submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/recessed medium class PVC conduit as required.					
a)	2X1.5sq.mm+ 1X1.5sq.mm earth wire	35	Metre			
b)	2X4sq.mm +1X4sq.mm earth wire	60	Metre			
3	Supplying and fixing of following size/ modules, GI/PVC box along with modular base & cover plate for modular switches in recess etc. as required.					
a)	6 Module	8	Nos			
b)	2 Module	5	Nos			
4	Supplying and fixing of following modular switch/socket on the existing modular plate & switch box including connections but excluding plate etc. as required.					
a)	5/6 amp switch	8	Nos.			
b)	3 pin 5/6 amp socket	8	Nos.			
c)	15/16A switch	9	Nos.			
d)	6pin 15/16A socket outlet	10	Nos.			
5	Installation, testing and commissioning of pre-wired, fluorescent fitting / compact fluorescent fitting of all types, complete with all accessories and tube etc. directly on ceiling/wall/false ceiling, including connection with 1.5sq.mm FRLS PVC insulated, copper conductor, single core cable and earthing etc. as required.	10	Nos.			

Item No.	Description	Qty	Unit	Rate (Rs.)	Amount (Rs)	Remarks
6	Supplying & Fixing of modular type 20Amp A.C. starter switch including 20A 3-Pin socket and plug top complete with GI Box recessed in wall.	1	Nos.			
7	Supply of Tube Light fittings as per PHILIPS CAT NO. TBS-669 M 2X TL5-28W EBT D6 with T-5, 28W lamp.	10	Nos.			
8	Installation,testing and commissioning of ceiling fan,including wiring the down rods of standard length (upto 30cm) with 1.5 sq.mm FRLS PVC insulated, copper conductor,single core cable etc.as required.	4	Nos.			
9	Supplying & Fixing two module stepped type electronic fan regulator on the existing modular plate switch box including connections but excluding modular plate etc.as required.	4	Nos.			
				Total		

(Signature of the bidder with date & stamp)