

Price Bid Format & Schedule of Work of NIT No.- IACS/WS/SB/2017-18/04, Date 17-04-2017						
Name of Work: Electrical Wiring Work for AC in Room Nos.-35, 56, 51B, 53A, 122A, 127A, situated in the Main Building of IACS						
Item No.	Description	Qty	Unit	Rate (Rs.)	Amount (Rs)	Remarks
1	Wiring for circuit/submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/recessed medium class PVC conduit as required. Make - Finolex, Havell's, KDK Evershine					
(a)	2X4sq.mm +1X4sq.mm earth wire	205	Metre			
2	Supplying and fixing of following size/ modules, GI/PVC box along with modular base & cover plate for modular switches in recess etc. as required. Make - Cabtree, North-West, MK					
(a)	2 Module	24	Nos			
3	Supplying & Fixing & making connections of modular type 20Amp A.C. starter switch in the existing modular switch box. Make - Cabtree, North-West, MK	12	Nos.			
4	Supplying and fixing 20A rating 240/415 V,10KA,"C" curve, miniature circuit breaker for inductive load of Single poles in the existing MCB DB complete with connections,testing and commissioning etc.as required. Make - Legrand, Hager, ABB					
(a)	Single pole	12	Nos.			
5	Supplying and fixing of following modular switch/socket on the existing modular plate & switch box including connections but excluding plate etc. as required.	12	Nos.			
				Total		