

| Schedule of Work                                                                                                                                                                            |                                                                                                                                                                                                                                               |     |       |              |             |         |
|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----|-------|--------------|-------------|---------|
| Name of Work: Dedicated Electrical Earthing for Room Nos. 150 & Lab in Biology Building Room No-14 and Earth connection from existing earth pit in Room No -93 in the Main Building of IACS |                                                                                                                                                                                                                                               |     |       |              |             |         |
| Item No.                                                                                                                                                                                    | Description                                                                                                                                                                                                                                   | Qty | Unit  | Rate (Rs.)   | Amount (Rs) | Remarks |
| 1                                                                                                                                                                                           | Earthing with copper earth plate 600 mm x 600mm x3mm thick including accessories and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7 metre long etc.with charcoal/coke and salt as required. | 2   | set   |              |             |         |
| 2                                                                                                                                                                                           | Providing & fixing of 25mm x 5mm copper strip (wrapped with PVC sleeve) in 40mm G.I pipe from earth electrode including connections with brass nut,bolt,spring washer excavation and refilling etc as required.                               | 110 | Metre |              |             |         |
| 3                                                                                                                                                                                           | Providing & fixing earth bus of 50 mm x 5mm copper strip on insulator surface for connections etc. as required.                                                                                                                               | 3   | Metre |              |             |         |
| 4                                                                                                                                                                                           | 1x16 sq.mm ISI marked,FR PVC insulated,single core copper conductor.                                                                                                                                                                          | 35  | Metre |              |             |         |
| 5                                                                                                                                                                                           | Supplying and laying of 25 mm diameter steel armoured flexible pvc conduit as required                                                                                                                                                        | 35  | Metre |              |             |         |
|                                                                                                                                                                                             |                                                                                                                                                                                                                                               |     |       |              |             |         |
|                                                                                                                                                                                             |                                                                                                                                                                                                                                               |     |       | <b>TOTAL</b> |             |         |
|                                                                                                                                                                                             | <b>(Rupees:-</b>                                                                                                                                                                                                                              |     |       |              |             |         |
| i)                                                                                                                                                                                          | <b>SAC No.</b>                                                                                                                                                                                                                                |     |       |              |             |         |
| ii)                                                                                                                                                                                         | <b>GST No.</b>                                                                                                                                                                                                                                |     |       |              |             |         |
| iii)                                                                                                                                                                                        | Please enclose <b>GST Registration</b>                                                                                                                                                                                                        |     |       |              |             |         |
|                                                                                                                                                                                             | <b>Note:-1.</b> The quoted rate shall be inclusive of all taxes & duties,levies,cess etc including <b>GST</b> also.Nothing extra will be paid to the contractor except the accepted rate and 2 ..i, & iii are mandetory.                      |     |       |              |             |         |