

Estimate & Schedule of Work						
Name of Work: Dedicated Earthing for LTHMFMS in Room No. 15 in the Main Building of IACS						
Item No.	Description	Qty	Unit	Rate (Rs.)	Amount (Rs)	Remarks
1	Earthing with copper earth plate 600 mm x 600mm x3mm thick including accessories and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7 metre long etc.with charcoal/coke and salt as required.	2	set			
2	Providing & fixing of 25mm x 5mm copper strip (wrapped with PVC sleeve) in 40mm G.I pipe from earth electrode including connections with brass nut,bolt,spring washer excavation and refilling etc as required.	60	Metre			
3	Providing & fixing earth bus of 50 mm x 5mm copper strip on insulator surface for connections etc. as required.	1	Metre			
4	Supply and laying of 1x16 sq.mm ISI marked,FRLS PVC insulated,single core copper conductor.	20	Metre			
5	Supplying and laying of 32 mm diameter steel armoured flexible pvc conduit as required	20	Metre			
				TOTAL		
	(Rupees:					
i)	SAC No.					
ii)	GST No.					
iii)	Please enclose GST Registration Certificate					
	Note:- The quoted rate shall be inclusive of all taxes & duties,levies,cess etc including GST also.Nothing extra will be paid to the contractor except the accepted rate and.i,ii & iii are mandetory.					