

Schedule of work					
Name of work: Dedicated earthing for Room no: - 81					
SL.No.	Item Description	Quantity.	Unit.	Rate (Rs.)	Amount (Rs.)
1	Earthing with copper earth plate 600 mm X 600 mm X 3 mm thick including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7 metre long etc. with charcoal/coke and salt as required.	1	Sets.		
2	Supplying and laying 25 mm X 5 mm copper strip wrapped with PVC sleeve at 0.5 metre below ground as strip earth electrode, including connection/terminating with ss nut bolt, spring washer etc as required. (Jointing shall be done by overlapping and with 2 sets of ss nut, bolt & spring washer spaced at 50 mm.)	25	Metre		
3	Providing and fixing earth bus of 50 mm X 5 mm with insulator on wall surface for connections etc. as required.	0.5	Metre		
				Total :	
Rupees.....Only					
NOTE: The quoted rate shall be inclusive of all taxes & duties, levies, cess etc i/c GST also. Nothing extra will be paid to the Contractor except the accepted rate.					
	GST No:				
	SAC code:				
	CGST@.....% considered in the above BOQ				
	SGST@.....% Considered in the above BOQ				