

Schedule of Work						
Name of Work: Electrical Renovation Work for Room No - M-259 in the Main Building of IACS						
Item No.	Description	Qty	Unit	Rate (Rs.)	Amount (Rs)	Remarks
1	Wiring for light point / fan point / exhaust fan point / call bell point with 1.5sq.mm FRLS PVC insulated copper conductor single core cable in surface / recessed medium class PVC conduit, with modular switch, modular plate , suitable GI box and earthing the point with 1.5 sq.mm. FRLS PVC insulated copper conductor single core cable etc. as required.					
	Group C (as per CPWD Categorisation)	12	Point			
2	Wiring for circuit/submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/recessed medium class PVC conduit as required.					
a)	2X4sq.mm +1X4sq.mm earth wire	280	Metre			
3	Supplying and fixing of following size/ modules, GI/PVC box along with modular base & cover plate for modular switches in recess etc. as required.					
a)	2 Module	6	Nos			
b)	6 Module	15	Nos			
4	Supplying and fixing of following modular switch/socket on the existing modular plate & switch box including connections but excluding plate etc. as required.					
a)	6 pin 15/16A Socket	33	Nos.			
b)	15/16 amp switch	30	Nos.			
5	Supply 2x40W,LED set wall mounting type LED light fitting (as per Philips cat no- BN100C LED40S - 6500PSU I120 GR with LED tube or equivalent model) complete with all accessories including connection with 1.5 sq.mm FRLS PVC insulated copper conductor ,single core cable and earthing etc. as required	10	Nos.			
6	Installation, testing and commissioning of pre-wired, LED fitting / compact Led fitting of all types, complete with all accessories and tube etc. directly on ceiling, including connection with 1.5sq.mm FRLS PVC insulated, copper conductor, single core cable and earthing etc. as required.	10	Nos.			
7	Supplying & Fixing of modular type 20Amp A.C. starter switch with GI/PVC Box complete surface/recessed in wall.	4	Nos.			

Item No.	Description	Qty	Unit	Rate (Rs.)	Amount (Rs)	Remarks
8	Supplying, fixing,connection,testing and commissioning of 48",1200 mm,Double ball bearing ceiling fan (Crompton greaves or equivalent make) with Regulator complete with all accessories ,hardwares,Regulator etc. as required.	2	No.			
9	Installation,testing and commissioning of wall mounting fan,with 1.5 sq.mm FRLS PVC insulated,copper conductor,single core cable etc.as required	2	No.			
10	Supplying and fixing following rating,40A double pole 240 volts, Isolator in the existing MCB DB complete with connections,testing and commissioning etc. as required.(Make-Havells or eqv.)	1	No			
11	Supplying and fixing following rating 415 volts, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections,testing and commissioning etc. as required.					
a)	16 A MCB, SP	4	Nos.			
				TOTAL		
	(Rupees.					
i)	GST No.-	GST%=		SGST%=		
ii)	SAC No.-					
iii)	Please enclosed GST Registration certificate copy					
	Note: The quoted rate shall be inclusive of all taxes & duties, levies, cess etc i/c GST also Nothing extra will be paid to the Contrator except the accepted rate.i,ii & iii mandatory.					