

Schedule of work					
Name of Work: Supply and fixing of GI earth strip for dedicated earthing in different locations of IACS, Jadavpur.					
Sl. No.	Description.	Quantity	Unit	Rate(Rs)	Amount (Rs.)
1	Providing and fixing 25 mm X 5 mm GI strip (wrapped with PVC sleeve) on insulator surface for connections etc.as required.	255	Meter		
2	Joining copper/GI tape (with another GI/ copper tape with the base of other metallic object by reveting/nut bolting/sweating and soldering etc., as required.	80	Nos.		
			TOTAL		
Rupees.....Only					
NOTE:The quoted rate shall be inclusive of all taxes & duties, levies, cess etc i/c GST also. Nothing extra will be paid to the Contractor except the accepted rate.					
GST No:					
HSN/SAC code:					
CGST@ 9% considered in the above BOQ					
SGST@ 9%Considered in the above BOQ					