

Schedule of work					
Name of Work: Supply, installation, testing and commissioning of 10 KVA UPS for CCTV server of IACS.					
Sl.N o.	Item description.	Quantity	Unit	Rate (Rs.)	Amount (Rs.)
1	Supply, installation, testing and commissioning of 10KVA, 3-Phase input and single phase output , double conversion online UPS, as per IEC 62040-3, according to the technical data sheet attached with the NIT, with two years warranty obligation.	1	No.		
	Make: Vertiv-liebert /Emerson /Schneider-APC/Legrand-Numeric				
2	Supply, Installation,Testing & Commissioning of 26Ah each, 12V SMF,VRLA battery along with supplying of 10 Sq.mm PVC insulated flexible copper wire for interconnection , jumper arrangement and termination, as required. (with 2-years warranty obligation)	20	Nos.		
	Make: Exide /Quanta				
3	Supplying of MS angle iron battery rack with suitable dimention (considering site constraint) for mounting 20 nos. 26AH batteries.	1	No.		
			Total :		
Rupees.....Only					
NOTE:The quoted rate shall be inclusive of all taxes & duties, levies, cess etc i/c GST also. Nothing extra will be paid to the Contractor except the accepted rate.					
GST No:					
HSN/SAC code:					
	CGST@ 14% for batteries and 9% for Rack and other electrical items are considered in the above BOQ				
	SGST@ 14% for batteries and 9% for Rack and other electrical items are considered in the above BOQ				