

Price Bid & Schedule of Work						
Name of Work: Electrical Wiring Work for Power supply of Acs in Room No. 126,97,107A,107B,25,32 in the Main Building of IACS as per NITNo.- IACS/WS/ELEC/2018-19/6, Dated 23-04-2018						
Item No.	Description	Qty	Unit	Rate (Rs.)	Amount (Rs)	Remarks
1	Wiring for circuit/submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor,single core cable in surface/recessed medium class PVC conduit as required. Make-Finolex,Havell's,KDK Evershine.					
(a)	2x4 sq.mm + 1x4 sq.mm	255	Mtr.			
2	Supplying & fixing of following size/ modules,GI/PVC box along with modular base & cover plate for modular switches in recess etc.as required.Make - Cabtree,North-West,MK.					
a)	2 Module	26	Nos.			
b)	6 Module	3	No.			
3	Supplying & fixing & making connections of modular type 20 amp A.C.starter switch in the existing modular switch box as required. Make - crabtree,North-west,MK	13	Nos.			
4	Supplying and fixing follwing modular switch/socket on the existing modular plate & switch box including connections but excluding modular plate etc.as required.					
(a)	6 pin 15/16 amp socket outlet with plug Top	19	Nos.			
(b)	15/16 amp switch	6	Nos.			
5	Supplying and fixing 20A,rating, 240/415V,10KA,"C" curve miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections,testing and commissioning etc as required.					
(a)	Single pole	16	Nos.			
6	Supplying and fixing of variable timer(National refrigeration make or equivalent make) to run both the AC periodically inside the room with complete connections,testing and commissioning etc. as required.	2	Nos.			
				TOTAL		
	Total :-Rupees					
i)	SAC No.					
ii)	GST No.					
iii)	Please enclose GST Registration Certificate copy					
	Note:- The quoted rate shall be inclusive of all taxes & duties,levies,cess etc including GST also.Nothing extra will be paid to the contractor except the accepted rate and.i,ii & iii are mandetory.					