

Schedule of Work						
Name of Work: Electrical Renovation Work Room No-85 situated in the Main Building of IACS						
Item No.	Description	Qty	Unit	Rate (Rs.)	Amount (Rs)	Remarks
1	Wiring for light point / fan point / exhaust fan point / call bell point with 1.5sq.mm FRLS PVC insulated copper conductor single core cable in surface / recessed medium class PVC conduit, with modular switch, modular plate , suitable GI box and earthing the point with 1.5 sq.mm. FRLS PVC insulated copper conductor single core cable etc. as required.					
	Group C (as per CPWD Categorisation)	8	Point			
2	Wiring for circuit/submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/recessed medium class PVC conduit as required.					
a)	2X1.5sq.mm+ 1X1.5sq.mm earth wire	10	Metre			
b)	2X4sq.mm +1X4sq.mm earth wire	200	Metre			
3	Supplying and fixing of following size/ modules, GI/PVC box along with modular base & cover plate for modular switches in recess etc. as required.					
a)	6 Module	12	Nos			
b)	3 Module	7	Nos			
c)	2 Module	6	Nos			
d)	8 Module	4	Nos			
4	Supplying and fixing of following modular switch/socket on the existing modular plate & switch box including connections but excluding plate etc. as required.					
a)	5/6 amp switch	26	Nos.			
b)	3 pin 5/6 amp socket	26	Nos.			
c)	6 pin 15/16A Socket	18	Nos.			
d)	15/16 amp switch	15	Nos.			
5	Supplying and fixing of following ways surface/recess mounting,vertical type,415V,TPN MCB distribution board of sheet steel,dust protected,duly powder painted,inclusive of 200A,tinned copper busbar,common neutral link,earth bar,din bar for mounting MCBs (but without MCBs and incomer) as required.					
	8 way(4+24),Double door	1	Nos.			

Item No.	Description	Qty	Unit	Rate (Rs.)	Amount (Rs)	Remarks
6	supplying & fixing of 5A to 32A rating,240/415v,10 KA,"C" curve,miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections,testing and commissioning etc,as required.					
(a)	single pole	24	Nos.			
7	Supply & fixing following rating ,four pole,415V,isolator in the existing MCB DB complete with connections,testing and commissioning etc. as required.					
(a)	63A	1	No.			
8	Supply 31W,Metal,Square(2"x2") recess mounting type LED light fitting (as per philips Cat. No. RC380B G4LED36S-6500PSU OD WH 31W or equivalent model) complete with all accessories including connection with 1.5 sq.mm FRLS PVC insulated copper conductor ,single core cable and earthing etc. as required	8	Nos.			
9 (a)	Installation, testing and commissioning of pre-wired, LED fitting / compact Led fitting of all types, complete with all accessories and tube etc. directly on ceiling, including connection with 1.5sq.mm FRLS PVC insulated, copper conductor, single core cable and earthing etc. as required.	8	Nos.			
9 (b)	Supplying & Fixing of modular type 20Amp A.C. starter switch with GI Box complete recessed in wall.	3	Nos.			
10	Supply & Fixing RJ11 Modular Type of Telephone Outlet in G.I. Box with cover, recessed in wall / Furniture.	1	No.			
				Total		
Rupees:-						
	Note:-The quoted rate shall be inclusive of GST and all other taxes (if any),duties,levies,cess etc.Nothing extra will be paid to the Contrctor except the accepted rate,and i,ii,iii is mandetory.(mentioned below)					
	% of CGST					
	% of SGST					
i)	GST No.					
ii)	SAC No.					
iii)	Please enclosed GST registration certificate copy					