

Schedule of work

Name of the work: Supply, installation, testing & Commissioning of intercom telephony system in the Lake view Building of IACS,Jadavpur.					
SI No:	Item description	Quantity	Unit	Rate(Rs.)	Amount(Rs.)
1	Supplying, laying & end termination of 0.5 mm dia, 50 pair, jelly filled, annealed copper conductor, FR-PVC insulated, armoured telephone cable	170	Meter		
	Make: Finolex/Netco/Nicco/Delton				
2	Supplying and fixing of 40 mm diameter steel conduit, along with accessories, in surface/recess including painting in case of surface conduit or cutting the surface and making good the same in case of recessed conduit.	55	Meter		
3	Supplying and installing of 50 Pair, metal telephone junction box duly powder coated,dust protected along with 2 X 50 pair base and modules fitted inside,including connection, testing & commissioning as required.	2	Nos.		
	Make: Krone				
4	supplying and fixing of single pair rozette box	15	Nos.		
5	Supplying and fixing of telephone hand set as per cat no: BPL 6390 or technically equivalent model of other approved manufacturer	15	Nos.		
	Make: Panasonic-KX-TS400SX/ Beitel				
				Total	
Rupees.....Only					
NOTE: The quoted rate shall be inclusive of all taxes & duties, levies, cess etc i/c GST also. Nothing extra will be paid to the Contractor except the accepted rate.					
	GST No:				
	SAC code:				
	CGST@.....% considered in the above BOQ				
	SGST@.....%Considered in the above BOQ				