

Schedule of work :					
Name of the work : Supply ,installation,testing & commissioning of PIR Occupancy Sensor in the corridor of the Main Building of IACS,Jadavpur.					
Sl.No.	Description.	Quantity	Unit	Rate(Rs.)	Amount (Rs)
1	Wiring for circuit/submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor,single core in surface/recessed medium class PVC conduit as required.				
	Make: Finolex/Havells/Polycab/Gloster				
a)	2X1.5 sq.mm.+ 1X 1.5 sq.mm.earth wire.	750	Metre.		
2	Supplying,installation,testing & commissioning of Infrared,Surface Mounted PIR occupancy Sensor with day light dimming in the false ceiling, compatible with the existing Havells make 15Watt LED lights (as per Crabtree Model No. ST46B, or equivalent model of other approved manufacturer.)	70	Nos.		
	Make: Crabtree,Philips,Wipro				
3	Supplying & fixing of 3 Pole 2.5 sq.mm.,16A connector.	70	Nos.		
				Total :	
Rupees.....only					
NOTE:The quoted rate shall be inclusive of all taxes & duties, levies, cess etc i/c GST also. Nothing extra will be paid to the Contractor except the accepted rate.					
	GST No:				
	SAC code:				
	CGST@.....% considered in the above BOQ				
	SGST@.....%Considered in the above BOQ				