

Schedule of work.

Name of work : Supply,installation,testing and commissioning of intercom telephoney system in the TRC Building, New Hostel buildings and other areas of 2B campus.					
Sl. No.	Description.	Quantity	Unit	Rate(Rs.)	Amount(Rs.)
1	Supplying of 0.5 mm dia, 200 pair, jelly filled,annealed copper conductor,FR-PVC insulated armoured telephone cable.	260	Meter		
	Make : Finolex/Netco/Nicco/Delton				
2	Supplying of 0.5 mm dia, 50 pair, jelly filled,annealed copper conductor,FR-PVC insulated armoured telephone cable.	225	Meter		
	Make : Finolex/Netco/Nicco/Delton.				
3	Supplying of 0.5 mm dia, 10 pair, jelly filled,annealed copper conductor,FR-PVC insulated armoured telephone cable.	290	Meter		
	Make : Finolex/Netco/Nicco/Delton.				
4	Laying of one number 0.5 mm dia,200 pair,annealed copper conductor,FR-PVC insulated armoured telephone cable direct in ground including excavation and refilling the trench etc as required,but excluding sand cushioning and protective covering.	100	Meter		
5	Laying of one number 0.5 mm dia,50 pair,annealed copper conductor,FR-PVC insulated armoured telephone cable direct in ground including excavation and refilling the trench etc as required,but excluding sand cushioning and protective covering.	30	Meter		
6	Laying of one number 0.5 mm dia,10 pair,annealed copper conductor,FR-PVC insulated armoured telephone cable direct in ground including excavation and refilling the trench etc as required,but excluding sand cushioning and protective covering.	100	Meter		
7	Supplying and laying of following size medium class GI pipe, along with all accessories like socket,bend, couplers etc. complete with fitting and cutting,jointing etc.,in the existing trench, complete as required				
a)	50 mm dia.	60	Meter		
b)	80 mm dia.	105	Meter		
8	Supplying and fixing of 200 pair, 2mm thick, CRCA sheet steel telephone junction box, duly powder coated painted ,dust protected along with 2 X 100 pair base and krone modules fitted inside, including connection, testing & commissioning etc. as required.	1	No.		
	Make : Krone.				

Sl. No.	Description.	Quantity	Unit	Rate(Rs.)	Amount(Rs.)
9	Supplying and fixing of 50 pair, 1.6 mm thick, CRCA sheet steel telephone junction box,duly power coated painted, dust protected along with 1 X 50 pair base and krone modules fitted inside, including connection, testing & commissioning etc. as required.	1	Nos.		
	Make : Krone.				
10	Supplying and fixing of 10 pair, 1.6 mm thick, CRCA sheet steel telephone junction box,duly power coated painted, dust protected along with 1 X 10 pair base and krone modules fitted inside, including connection, testing & commissioning etc. as required.	3	Nos.		
	Make : Krone.				
11	Supplying and fixing of single pair rozette box.	60	Nos.		
12	Supplying and fixing of telephone hand set as per cat no. : BPL 6390 or equivalent model of other approved manufacturar.	60	Nos.		
	Make : Panasonic - KX - TS400SX./BPL				
				Total :	
Rupees.....Only					
NOTE:The quoted rate shall be inclusive of all taxes & duties, levies, cess etc i/c GST also. Nothing extra will be paid to the Contractor except the accepted rate.					
	GST No:				
	SAC code:				
	CGST@.....% considered in the above BOQ				
	SGST@.....%Considered in the above BOQ				