

Schedule of Work						
Name of Work: Electrical Renovation Work for ROOM Nos.-144,3(65),150 situated in the Main Building of IACS						
Item No.	Description	Qty	Unit	Rate (Rs.)	Amount (Rs)	Remarks
1	Wiring for light point / fan point / exhaust fan point / call bell point with 1.5sq.mm FRLS PVC insulated copper conductor single core cable in surface / recessed medium class PVC conduit, with modular switch, modular plate , suitable GI box and earthing the point with 1.5 sq.mm. FRLS PVC insulated copper conductor single core cable etc. as required.					
	Group C (as per CPWD Categorisation)	11	Point			
2	Wiring for circuit/submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/recessed medium class PVC conduit as required.					
a)	2X6 sq.mm+ 1X6 sq.mm earth wire	10	Metre			
b)	2X4sq.mm +1X4sq.mm earth wire	100	Metre			
3	Supplying and fixing of following size/ modules, GI/PVC box along with modular base & cover plate for modular switches in recess etc. as required.					
a)	2 Module	2	Nos			
b)	6 Module	16	Nos			
4	Supplying and fixing of following modular switch/socket on the existing modular plate & switch box including connections but excluding plate etc. as required.					
a)	6 pin 15/16A Socket	54	Nos.			
b)	15/16 amp switch	53	Nos.			
5	Supply 36W, double tube light set with LED light (as per philips Cat. No. TMC-501P with 2nos. 18W master LED length 1200mm,2100lumen or equivalent model) complete with all accessories including connection with 1.5 sq.mm FRLS PVC insulated copper conductor ,single core cable and earthing etc. as	6	Nos.			
6	Supply 36W,Metal,Square(2'x2') recess mounting type LED light fitting (as per crompton Aura I Cat. No. LCPL-36-CDL(2x2) with LED tube or equivalent model) complete with all accessories including connection with 1.5 sq.mm FRLS PVC insulated copper conductor ,single core cable and earthing etc. as required	1	No.			
7	Supplying & Fixing of modular type 25Amp A.C. starter switch with GI/PVC Box complete surface/recessed in wall.	1	Nos.			

Item No.	Description	Qty	Unit	Rate (Rs.)	Amount (Rs)	Remarks
8	Installation, testing and commissioning of pre-wired, LED fitting / compact Led fitting of all types, complete with all accessories and tube etc. directly on ceiling, including connection with 1.5sq.mm FRLS PVC insulated, copper conductor, single core cable and earthing etc. as required.	7	Nos.			
	XLPE armoured Al. cable: -					
9	Supplying of XLPE insulated and PVC sheathed armoured heavy duty aluminium conductor cable of CC/Universal/POLYCAB make 1.1KV grade as per relevant IS specifications for the following sizes:					
a)	4cx16 sq.mm	20	mt.			
10	Laying & Fixing of 1no. PVC insulated and PVC sheathed/XLPE power cable of 1.1KV Grade of following size on wall surface as required.					
a)	4cx16 sq.mm (clamped with 1mm thick saddle)	20	mt.			
11	Cable Termination: -					
	Supplying and making end termination with brass compressor gland and copper lugs for following size of XLPE insulated and (PVC sheathed aluminium conductor cable of 1.1KV grade as required).					
a)	4cx16 sq.mm	2	nos.			
12	Providing & Fixing 4mm dia copper wire on surface/recess for loop earthing along with existing surface/recessed conduit/submain wiring/cable as required.	40	mt.			
13	Supplying and fixing following rating 230 volts, 1200 mm 3 blade Aluminium body, Antidust category ball bearing with copper winding ceiling fan (Model-Crompton Aura or Equivalent) to be hanged from the ceiling with appropriate down rod.	2	nos.			
14	Installation, testing and commissioning of ceiling fan, including wiring the down rods of standard length (upto 30 cm) with 1.5 sq.mm FRLS PVC insulated , copper conductor , single core cable etc. as required.	2	nos.			
15	Supplying and fixing following rating 415 volts, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required.					
a)	10 A MCB, SP	2	No..			
b)	20 A MCB, SP	5	Nos.			
c)	16 A MCB, SP	5	Nos.			
e)	32 A MCB DP	4	No.			

Item No.	Description	Qty	Unit	Rate (Rs.)	Amount (Rs)	Remarks
16	supply and fixing of following way,horizontal type three pole and neutral,sheet steel,MCB distribution board 415V,on surface/recess,complete with tinned copper bus bar,neutral bus bar,earth bar,din bar,interconnections ,powder painted including earthing etc.as required (But excluding MCB/RCCB/Isolator)					
a)	4 way(4+12),Double door	1	No.			
17	Supplying and fixing following rating four pole 415V, 10KA "C" curve minature circuit breaker suitable for inductive load in the existing MCB DB complete with connections,testing and commissioning etc.as					
a)	63A, 4P MCB	1	No.			
18	Supplying and fixing of variable timer(National refrigeration make or BSC make or equivalent make) to run both the AC periodically inside the room with complete connections,testing and commissioning etc. as required.	1				
19	supply and fixing of DP sheet steel enclosure on surface/recess along with 32A 240 V "C" curve DP MCB complete with connections,testing and commissioning etc. as required.	4	No.			
	.			TOTAL		
	Total:-					
i)	GST No.-					
ii)	SAC No.-					
iii)	Please enclosed GST Registration certificate copy					
	Note: The quoted rate shall be inclusive of all taxes & duties,levies,cess etc i/c GST also Nothing extra will be paid to the Contrator except the accepted rate.(i),(ii) & (iii) are mandetory .					